

Road Commission for Oakland County
Preliminary Cost Estimate
4/24/2026

Dixie Hwy, Grange Hall Rd to I-75
Groveland Twp

Location: Dixie Hwy, Grange Hall Rd to I-75
Description: Cold-In-Place recycling of HMA pavement; upgrade existing guardrail; 3.5" HMA overlay
Length: 28,333 ft

Preliminary Cost Estimate

Total Construction	\$6,813,000
Total Cost	\$6,813,000

Notes:

- 1) This estimate is not the result of a detailed survey & design, and is approximation only.
- 2) Preliminary engineering includes initial survey, design, and plan preparation.
Construction engineering includes project administration, staking, inspection, and material testing.

Prepared by:
D. Todd White, P.E.
Programming Engineer
Road Commission for Oakland County

ROAD COMMISSION FOR OAKLAND COUNTY COST ESTIMATE

Project:	Dixie Hwy, Grange Hall Rd to I-75
Location:	Groveland Twp
Length:	28,333 ft
Cold-In-Place recycling of HMA pavement; upgrade existing guardrail; 3.5" HMA overlay	

PROJECT ACTIVITY						Share of
Activity Details		Quantities	Units	Unit Costs	Detail Costs	CON TOTAL
CON						
SITE PREPARATION:						
	Remove Existing Pavement	-	SYD	\$ 15.00	\$ -	
	Remove Existing Curb	-	LFT	\$ 18.00	\$ -	
	Remove Sewer	-	LFT	\$ 8.00	\$ -	
	Clearing & Grub Land	-	Acre	\$ 5,000.00	\$ -	
	Tree Removal	-	EA	\$ 750.00	\$ -	
	Erosion Control	1	LS	\$ 40,000.00	\$ 40,000.00	
Other:	Misc Site Prep		LS	\$ -	\$ -	\$ 40,000.00 0.7%
EARTHWORK:						
	Undercutting	-	CYD	\$ 15.00	\$ -	
	Sub-Base (Sand)	-	CYD	\$ 10.00	\$ -	
	Base (Stone)	-	CYD	\$ 20.00	\$ -	
	Earth Excavation	-	CYD	\$ 35.00	\$ -	
	Embankment	-	CYD	\$ 35.00	\$ -	
	Peat Excavation and Backfill	-	LS	\$ -	\$ -	
Other:		-	LS	\$ -	\$ -	\$ - 0.0%
DRAINAGE:						
	Sewers	-	LFT	\$ 50.00	\$ -	
	Culverts	-	LFT	\$ 25.00	\$ -	
	Edge Drains	-	LFT	\$ 10.00	\$ -	
	Adj. Basins & Structures	-	EA	\$ 2,000.00	\$ -	
	New Basins & Structures	-	EA	\$ 2,400.00	\$ -	
Other:	Misc. Drainage	1	LS	\$ 130,000.00	\$ 130,000.00	\$ 130,000.00 2.3%
PAVEMENT RESTORATION:						
	Base Repair	-	SYD	\$ 50.00	\$ -	
	Crack & Seat Pavement	-	SYD	\$ 0.50	\$ -	
	Joint Repairs (Details 7 & 8)	-	LFT	\$ 5.00	\$ -	
	Hand Patching for Joint Repairs	-	Ton	\$ 110.00	\$ -	
	Slab Replacement	-	SYD	\$ 35.00	\$ -	
	CIP Recycling (3.5")	139,000	SYD	\$ 7.00	\$ 973,000.00	
	Overlay HMA 3.5 Inch	27,000	Ton	\$ 140.00	\$ 3,780,000.00	
	Overlay PCC 5 Inch	-	SYD	\$ 105.00	\$ -	
	HMA Separator 1 Inch	-	Ton	\$ 75.00	\$ -	
	Driveways	-	EA	\$ 1,500.00	\$ -	
	ADA Ramps	-	EA	\$ 1,000.00	\$ -	
Other:	Misc		LS	\$ -	\$ -	\$ 4,753,000.00 83.7%
NEW PAVEMENT:						
	Curb & Gutter	-	LFT	\$ 25.00	\$ -	
	Pavement - HMA 6 Inch	77	Ton	\$ 140.00	\$ 10,780.00	
	Pavement - PCC 10 Inch	-	SYD	\$ 75.00	\$ -	
	Aggregate Base, 21AA 8 Inch	52	Ton	\$ 20.00	\$ 1,037.04	
	Paved Shoulders - HMA 6 Inch	77	Ton	\$ 85.00	\$ 6,545.00	
	Paved Shoulders - PCC 6 Inch	167	SYD	\$ -	\$ -	
	Gravel Shoulders 6 Inch	-	Ton	\$ 25.00	\$ -	
Other:	Misc. Pavement		LS	\$ -	\$ -	\$ 18,362.04 0.3%

PROJECT ACTIVITY						Share of
Activity Details	Quantities	Units	Unit Costs	Detail Costs	ACTIVITY COSTS	CON TOTAL
WORK ZONE TRAFFIC CONTROL:				[Usually ranges from 6 to 10 percent of CON total]		
Arrow Boards	-	EA	\$ 5,000.00	\$ -		
PCM Signs	-	EA	\$ 10,000.00	\$ -		
Attenuators, Mobile	-	EA	\$ -	\$ -		
Temp Concrete Barrier Walls	-	LFT	\$ -	\$ -		
Barricades	-	EA	\$ 500.00	\$ -		
Plastic Drums	-	EA	\$ 40.00	\$ -		
Flagger Control	-	LS	\$ -	\$ -		
Pavement Markings	-	LFT	\$ 0.50	\$ -		
Signals & Electrical	-	LS	\$ 10,000.00	\$ -		
Traffic & Detour Signs	-	LS	\$ 60,000.00	\$ -		
Other: Misc. Traffic Control	1	LS	\$ 350,000.00	\$ 350,000.00	\$ 350,000.00	6.2%
PERMANENT TRAFFIC CONTROL:						
Signs	-	LS	\$ 25,000.00	\$ -		
Signals	-	EA	\$ 475,000.00	\$ -		
Pavement Markings	-	LFT	\$ 1.00	\$ -		
Guard Rail, Type B	1,200	LFT	\$ 50.00	\$ 60,000.00		
Other:	1	LS	\$ 150,000.00	\$ 150,000.00	\$ 210,000.00	3.7%
PUBLIC UTILITY RELOCATION:						
Fire Hydrants	-	EA	\$ -	\$ -		
Other:	1	LS	\$ 100,000.00	\$ 100,000.00	\$ 100,000.00	1.8%
RESTORATION:						
Topsoil	Inch	SYD	\$ -	\$ -		
Seed & Mulch		SYD	\$ -	\$ -		
Sod		SYD	\$ -	\$ -		
Restoration	-	SYD	\$ 15.00	\$ -		
Other Restoration	1	LS	\$ 75,000.00	\$ 75,000.00	\$ 75,000.00	1.3%
MISCELLANEOUS:						
Mobilization (10%)	1	LS	570,000	\$ 570,000.00		
Other Miscellaneous	-	LS	\$ -	\$ -	\$ 570,000.00	10.0%
SUB-TOTAL CONSTRUCTION:					\$ 5,677,000.00	
CONTINGENCY (20% of Sub-total):					\$ 1,136,000.00	
TOTAL CONSTRUCTION PHASE (Sub-Total + Contingency):					\$ 6,813,000.00	

Prepared By: D. Todd White, P.E.
4/24/2026

NOTE: 1) This estimate is not the result of a detailed survey and design, and is approximate only.
2) Preliminary engineering is estimated at 10% of the construction cost and construction engineering is estimated at 15% of the construction cost.