

**Road Commission for Oakland County**  
**Preliminary Cost Estimate**  
**4/24/2026**

**Dixie Hwy, N. of Oak Hill Rd to N. of Grange Hall Rd**  
**Groveland Twp**

---

**Location:** Dixie Hwy, N. of Oak Hill Rd to N. of Grange Hall Rd  
**Description:** Cold-In-Place recycling of HMA pavement; upgrade existing guardrail; 3.5" HMA overlay  
**Length:** 15,140 ft

---

Preliminary Cost Estimate

|                    |                    |
|--------------------|--------------------|
| Total Construction | \$4,228,000        |
| <b>Total Cost</b>  | <b>\$4,228,000</b> |

---

**Notes:**

- 1) This estimate is not the result of a detailed survey & design, and is approximation only.
- 2) Preliminary engineering includes initial survey, design, and plan preparation.  
Construction engineering includes project administration, staking, inspection, and material testing.

Prepared by:  
D. Todd White, P.E.  
Programming Engineer  
Road Commission for Oakland County

# ROAD COMMISSION FOR OAKLAND COUNTY COST ESTIMATE

|                                                                                              |                                                             |
|----------------------------------------------------------------------------------------------|-------------------------------------------------------------|
| Project:                                                                                     | <b>Dixie Hwy, N. of Oak Hill Rd to N. of Grange Hall Rd</b> |
| Location:                                                                                    | <b>Groveland Twp</b>                                        |
| Length:                                                                                      | <b>15,140 ft</b>                                            |
| <b>Cold-In-Place recycling of HMA pavement; upgrade existing guardrail; 3.5" HMA overlay</b> |                                                             |

| PROJECT ACTIVITY                |            |       |               |                 |                 | Share of  |
|---------------------------------|------------|-------|---------------|-----------------|-----------------|-----------|
| Activity Details                | Quantities | Units | Unit Costs    | Detail Costs    | ACTIVITY COSTS  | CON TOTAL |
| <b>CON</b>                      |            |       |               |                 |                 |           |
| SITE PREPARATION:               |            |       |               |                 |                 |           |
| Remove Existing Pavement        | -          | SYD   | \$ 15.00      | \$ -            |                 |           |
| Remove Existing Curb            | -          | LFT   | \$ 18.00      | \$ -            |                 |           |
| Remove Sewer                    | -          | LFT   | \$ 8.00       | \$ -            |                 |           |
| Clearing & Grub Land            | -          | Acre  | \$ 5,000.00   | \$ -            |                 |           |
| Tree Removal                    | -          | EA    | \$ 750.00     | \$ -            |                 |           |
| Erosion Control                 | 1          | LS    | \$ 20,000.00  | \$ 20,000.00    |                 |           |
| Other: Misc Site Prep           |            | LS    | \$ -          | \$ -            | \$ 20,000.00    | 0.6%      |
| EARTHWORK:                      |            |       |               |                 |                 |           |
| Undercutting                    | -          | CYD   | \$ 15.00      | \$ -            |                 |           |
| Sub-Base (Sand)                 | -          | CYD   | \$ 10.00      | \$ -            |                 |           |
| Base (Stone)                    | -          | CYD   | \$ 20.00      | \$ -            |                 |           |
| Earth Excavation                | -          | CYD   | \$ 35.00      | \$ -            |                 |           |
| Embankment                      | -          | CYD   | \$ 35.00      | \$ -            |                 |           |
| Peat Excavation and Backfill    | -          | LS    | \$ -          | \$ -            |                 |           |
| Other:                          | -          | LS    | \$ -          | \$ -            | \$ -            | 0.0%      |
| DRAINAGE:                       |            |       |               |                 |                 |           |
| Sewers                          | -          | LFT   | \$ 50.00      | \$ -            |                 |           |
| Culverts                        | -          | LFT   | \$ 25.00      | \$ -            |                 |           |
| Edge Drains                     | -          | LFT   | \$ 10.00      | \$ -            |                 |           |
| Adj. Basins & Structures        | -          | EA    | \$ 2,000.00   | \$ -            |                 |           |
| New Basins & Structures         | -          | EA    | \$ 2,400.00   | \$ -            |                 |           |
| Other: Misc. Drainage           | 1          | LS    | \$ 100,000.00 | \$ 100,000.00   | \$ 100,000.00   | 2.8%      |
| PAVEMENT RESTORATION:           |            |       |               |                 |                 |           |
| Base Repair                     | -          | SYD   | \$ 50.00      | \$ -            |                 |           |
| Crack & Seat Pavement           | -          | SYD   | \$ 0.50       | \$ -            |                 |           |
| Joint Repairs (Details 7 & 8)   | -          | LFT   | \$ 5.00       | \$ -            |                 |           |
| Hand Patching for Joint Repairs | -          | Ton   | \$ 110.00     | \$ -            |                 |           |
| Slab Replacement                | -          | SYD   | \$ 35.00      | \$ -            |                 |           |
| CIP Recycling (3.5")            | 80,000     | SYD   | \$ 7.00       | \$ 560,000.00   |                 |           |
| Overlay HMA 3.5 Inch            | 15,400     | Ton   | \$ 140.00     | \$ 2,156,000.00 |                 |           |
| Overlay PCC 5 Inch              | -          | SYD   | \$ 105.00     | \$ -            |                 |           |
| HMA Separator 1 Inch            | -          | Ton   | \$ 75.00      | \$ -            |                 |           |
| Driveways                       | -          | EA    | \$ 1,500.00   | \$ -            |                 |           |
| ADA Ramps                       | -          | EA    | \$ 1,000.00   | \$ -            |                 |           |
| Other: Misc                     |            | LS    | \$ -          | \$ -            | \$ 2,716,000.00 | 77.1%     |
| NEW PAVEMENT:                   |            |       |               |                 |                 |           |
| Curb & Gutter                   | -          | LFT   | \$ 25.00      | \$ -            |                 |           |
| Pavement - HMA 6 Inch           | -          | Ton   | \$ 140.00     | \$ -            |                 |           |
| Pavement - PCC 10 Inch          | -          | SYD   | \$ 75.00      | \$ -            |                 |           |
| Aggregate Base, 21AA 8 Inch     | -          | Ton   | \$ 20.00      | \$ -            |                 |           |
| Paved Shoulders - HMA 6 Inch    | -          | Ton   | \$ 85.00      | \$ -            |                 |           |
| Paved Shoulders - PCC 6 Inch    | -          | SYD   | \$ -          | \$ -            |                 |           |
| Gravel Shoulders 6 Inch         | -          | Ton   | \$ 25.00      | \$ -            |                 |           |
| Other: Misc. Pavement           |            | LS    | \$ -          | \$ -            | \$ -            | 0.0%      |

| PROJECT ACTIVITY                                    |            |       |               |                                                    |                 | Share of  |
|-----------------------------------------------------|------------|-------|---------------|----------------------------------------------------|-----------------|-----------|
| Activity Details                                    | Quantities | Units | Unit Costs    | Detail Costs                                       | ACTIVITY COSTS  | CON TOTAL |
| WORK ZONE TRAFFIC CONTROL:                          |            |       |               | [Usually ranges from 6 to 10 percent of CON total] |                 |           |
| Arrow Boards                                        | -          | EA    | \$ 5,000.00   | \$ -                                               |                 |           |
| PCM Signs                                           | -          | EA    | \$ 10,000.00  | \$ -                                               |                 |           |
| Attenuators, Mobile                                 | -          | EA    | \$ -          | \$ -                                               |                 |           |
| Temp Concrete Barrier Walls                         | -          | LFT   | \$ -          | \$ -                                               |                 |           |
| Barricades                                          | -          | EA    | \$ 500.00     | \$ -                                               |                 |           |
| Plastic Drums                                       | -          | EA    | \$ 40.00      | \$ -                                               |                 |           |
| Flagger Control                                     | -          | LS    | \$ -          | \$ -                                               |                 |           |
| Pavement Markings                                   | -          | LFT   | \$ 0.50       | \$ -                                               |                 |           |
| Signals & Electrical                                | -          | LS    | \$ 10,000.00  | \$ -                                               |                 |           |
| Traffic & Detour Signs                              | -          | LS    | \$ 60,000.00  | \$ -                                               |                 |           |
| Other: Misc. Traffic Control                        | 1          | LS    | \$ 200,000.00 | \$ 250,000.00                                      | \$ 250,000.00   | 7.1%      |
| PERMANENT TRAFFIC CONTROL:                          |            |       |               |                                                    |                 |           |
| Signs                                               | -          | LS    | \$ 25,000.00  | \$ -                                               |                 |           |
| Signals                                             | -          | EA    | \$ 475,000.00 | \$ -                                               |                 |           |
| Pavement Markings                                   | -          | LFT   | \$ 1.00       | \$ -                                               |                 |           |
| Guard Rail, Type B                                  | 3,735      | LFT   | \$ 50.00      | \$ 186,750.00                                      |                 |           |
| Other:                                              | 1          | LS    | \$ 100,000.00 | \$ 100,000.00                                      | \$ 286,750.00   | 8.1%      |
| PUBLIC UTILITY RELOCATION:                          |            |       |               |                                                    |                 |           |
| Fire Hydrants                                       | -          | EA    | \$ -          | \$ -                                               |                 |           |
| Other:                                              | 1          | LS    | \$ 100,000.00 | \$ 100,000.00                                      | \$ 100,000.00   | 2.8%      |
| RESTORATION:                                        |            |       |               |                                                    |                 |           |
| Topsoil                                             | Inch       | SYD   | \$ -          | \$ -                                               |                 |           |
| Seed & Mulch                                        |            | SYD   | \$ -          | \$ -                                               |                 |           |
| Sod                                                 |            | SYD   | \$ -          | \$ -                                               |                 |           |
| Restoration                                         | -          | SYD   | \$ 15.00      | \$ -                                               |                 |           |
| Other Restoration                                   | 1          | LS    | \$ 50,000.00  | \$ 50,000.00                                       | \$ 50,000.00    | 1.4%      |
| MISCELLANEOUS:                                      |            |       |               |                                                    |                 |           |
| Mobilization (10%)                                  | 1          | LS    | 360,000       | \$ 360,000.00                                      |                 |           |
| Other Miscellaneous                                 | -          | LS    | \$ -          | \$ -                                               | \$ 360,000.00   | 10.2%     |
| SUB-TOTAL CONSTRUCTION:                             |            |       |               |                                                    | \$ 3,523,000.00 |           |
| CONTINGENCY (20% of Sub-total):                     |            |       |               |                                                    | \$ 705,000.00   |           |
| TOTAL CONSTRUCTION PHASE (Sub-Total + Contingency): |            |       |               |                                                    | \$ 4,228,000.00 |           |

Prepared By: D. Todd White, P.E.  
4/24/2026

NOTE: 1) This estimate is not the result of a detailed survey and design, and is approximate only.  
2) Preliminary engineering is estimated at 10% of the construction cost and construction engineering is estimated at 15% of the construction cost.